



SCHEDULE NUMBER

Nominal Pipe Size	O D Inches	Data	*Non Scheduled Pipe														
			10	N/S*	20	30	40	STD	60	80	XH	100	120	140	160	XXH	
1/8	0.405	wall					0.068	0.068			0.095	0.095					
		# / ft					0.24	0.24			0.31	0.31					
1/4	0.540	wall					0.088	0.088			0.119	0.119					
		# / ft					0.43	0.43			0.54	0.54					
3/8	0.675	wall					0.091	0.091			0.126	0.126					
		# / ft					0.57	0.57			0.74	0.74					
1/2	0.840	wall					0.109	0.109			0.147	0.147				0.188	0.294
		# / ft					0.85	0.85			1.09	1.09				1.31	1.72
3/4	1.050	wall					0.113	0.113			0.154	0.154				0.219	0.308
		# / ft					1.13	1.13			1.48	1.48				1.95	2.44
1	1.315	wall					0.133	0.133			0.179	0.179				0.250	0.358
		# / ft					1.68	1.68			2.17	2.17				2.85	3.66
1 1/4	1.660	wall	0.109				0.140	0.140			0.191	0.191				0.250	0.382
		# / ft	1.81				2.27	2.27			3.00	3.00				3.77	5.22
1 1/2	1.900	wall	0.109				0.145	0.145			0.200	0.200				0.281	0.400
		# / ft	2.09				2.72	2.72			3.63	3.63				4.86	6.41
2	2.375	wall	0.109				0.154	0.154			0.218	0.218				0.344	0.436
		# / ft	2.64				3.66	3.66			5.03	5.03				7.47	9.04
2 1/2	2.875	wall	0.120				0.203	0.203			0.276	0.276				0.375	0.552
		# / ft	3.53				5.80	5.80			7.67	7.67				10.02	13.71
3	3.500	wall	0.120				0.216	0.216			0.300	0.300				0.438	0.600
		# / ft	4.34				7.58	7.58			10.26	10.26				14.34	18.60
3 1/2	4.000	wall	0.120				0.226	0.226			0.318	0.318					
		# / ft	4.98				9.12	9.12			12.52	12.52					
4	4.500	wall	0.120	0.188			0.237	0.237			0.337	0.337		0.438		0.531	0.674
		# / ft	5.62	8.67			10.80	10.80			15.00	15.00		19.02		22.53	27.57
5	5.563	wall	0.134				0.258	0.258			0.375	0.375		0.500		0.625	0.750
		# / ft	7.78				14.63	14.63			20.80	20.80		27.06		32.99	38.59
6	6.625	wall	0.134	0.188	0.250		0.280	0.280			0.432	0.432		0.562		0.719	0.864
		# / ft	9.30	12.94	17.04		18.99	18.99			28.60	28.60		36.43		45.39	53.21
8	8.625	wall	0.148	0.188	0.250	0.277	0.322	0.322	0.406	0.500	0.500	0.594	0.719	0.812	0.906	0.975	0.875
		# / ft	13.41	16.96	22.38	24.72	28.58	28.58	35.67	43.43	43.43	51.00	60.77	67.82	74.76	72.49	72.49
10	10.750	wall	0.165	0.188	0.250	0.307	0.365	0.365	0.500	0.594	0.500	0.719	0.844	1.000	1.125	1.000	1.000
		# / ft	18.67	21.23	28.06	34.27	40.52	40.52	54.79	64.49	54.79	77.10	89.38	104.23	115.75	104.23	104.23
12	12.750	wall	0.180	0.188	0.250	0.330	0.406	0.375	0.562	0.688	0.500	0.844	1.000	1.125	1.312	1.000	1.000
		# / ft	24.19	25.25	33.41	43.81	53.57	49.61	73.22	88.71	65.48	107.42	125.61	139.81	160.42	125.61	125.61
14	14.000	wall	0.250			0.312	0.375	0.438	0.375	0.594	0.750	0.500	0.938	1.094	1.250	1.406	
		# / ft	36.75			45.65	54.62	63.50	54.62	85.13	106.23	72.16	130.98	150.93	170.37	189.29	
16	16.000	wall	0.250			0.312	0.375	0.500	0.375	0.656	0.844	0.500	1.031	1.219	1.438	1.594	
		# / ft	42.09			52.32	62.64	82.85	62.64	107.60	136.74	82.85	164.98	192.61	223.85	245.48	
18	18.000	wall	0.250			0.312	0.438	0.562	0.375	0.750	0.938	0.500	1.156	1.375	1.562	1.781	
		# / ft	47.44			58.99	82.23	104.76	70.65	138.30	171.08	93.54	208.15	244.37	274.48	308.79	
20	20.000	wall	0.250			0.375	0.500	0.594	0.375	0.812	1.031	0.500	1.281	1.500	1.750	1.969	
		# / ft	52.78			78.67	104.23	123.23	78.67	166.56	209.06	104.23	256.34	296.55	341.41	379.53	
24	24.000	wall	0.250			0.375	0.562	0.688	0.375	0.969	1.219	0.500	1.531	1.812	2.062	2.344	
		# / ft	63.47			94.71	140.81	171.45	94.71	238.57	296.86	125.61	367.74	429.79	483.57	542.64	
30	30.000	wall	0.312			0.500			0.375			0.500					
		# / ft	99.02			157.68			118.76			157.68					
36	36.000	wall	0.312			0.500			0.375								
		# / ft	119.03			189.75			142.81								